

BRUHAT BANGALORE MAHANAGAR PALIKE					
Project Division, Yelahanka Zone					
MODIFIED SCHEDULE - B					
Development of parks and Construction of Toilets at B sector Parks in Ward No.04 Yelahanka New Town					
Work Order No: EE (Project)/Ynk Zone/WO/ 08/2020-21 Dt:- 29/04/2020					
SL.No	Quantity	Item Name	Unit	Approved Rates of Sri. GOPIREDDY	
				In figures	In words
1	3847.09	KSRRB 200-8. Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials labour charges complete as per specifications. MORTH / Chapter 2 (P.No.138, I.No.18.11 of PW, P&IWTDR SR 2018-19)	Sqm	11.13	Rupees Eleven And Paise Thirteen Only
2	640.94	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3 (P.No.143, I.No.19.1 of PW, P&IWTDR SR 2018-19)	Cum	222.36	Rupees Two Hundred Twenty Two And Paise Thirty Six Only
	139.61	Above 125%	Cum	222.36	Rupees Two Hundred Twenty Two And Paise
3	93.63	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. MORTH Specification No. 2100 (P.No.222, I.No.27.18 of PW,P&IWTDR S.R 2018-19)	Cum	5692.45	Rupees Five Thousand Six Hundred Ninety Two And Paise Forty Five Only
	13.74	Above 125%	Cum	5692.45	Rupees Five Thousand Six Hundred Ninety
4	205.04	KSRB 5.4-3 : Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:6 , edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, scaffolding, curing complete as per specifications. KBS 5.1.13 (Page No. 23, Item No. - 5.12 of PW;P&IWTDR S.R 2018-19)	Cum	5841.58	Rupees Five Thousand Eight Hundred Forty One And Paise Fifty Eight Only
	106.85	Above 125%	Cum	5841.58	Rupees Five Thousand Eight Hundred Forty One
5	260.81	KSRB 15.1.3 - do - Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	111.12	Rupees One Hundred Eleven And Paise Twelve Only
	241.53	Above 125%	Sqm	111.12	Rupees One Hundred Eleven And Paise Twelve

6	59.15	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No. 4.6 of PW, P&IWTDR SR2016-17)	Cum	6169.51	Rupees Six Thousand One Hundred Sixty Nine And Paise Fifty One Only
	22.77	Above 125%	Cum	6169.51	Rupees Six Thousand One Hundred Sixty
7	126.29	KSRB 14.3 : Providing and laying flooring and steps machine cut granite slabs 40mm thick on cement mortar bed 1:6, 25 mm thick, and pointed with cement mortar 1:3 over existing cement concrete bed, including cost of materials, mortar, labour, curing complete as per specifications. Specification No. KBS 14.26 (P.No103 of I.No.14.3 in PW,P&IWTDR SR 2018-19)	Sqm	2700.99	Rupees Two Thousand Seven Hundred And Paise Ninety Nine Only
8	305.72	Providing and fixing for flooring 20mm thick gang saw water cut sadharhalli gray granite in CM 1:4 proportion, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, grooves in joints including cost of curing - minimum width of 900mm. (P.No 112, I.No.14.61.2 of PW,P&IWTDR S.R 2018-19)	Sqm	2202.42	Rupees Two Thousand Two Hundred Two And Paise Forty Two Only
9	14.74	KSRRB M2200-5.9. Providing and laying Design mix M20 with OPC @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplasticiser @3lts conforming to IS9103-1999 Reaffirmed-2008 including cost of materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. - i) Upto 5 m height.(P.No.227, I.No.28.7.9 of PW, P&IWTDR SR 2018-19)	Cum	5757.00	Rupees Five Thousand Seven Hundred Fifty Seven Only
	2.85	Above 125%	Cum	5757.00	Rupees Five Thousand Seven Hundred Fifty
10	420.79	KSRRB M400-19: Construction of Median and island above road level with approved material deposited from borrowpits, spread, sloped and compacted as per Clause 400.7 complete as per specifications. MORTH Specification No.407 (P.No155 of I.No.20.20 in PW,P&IWTDR SR 2018-19)	cum	232.59	Rupees Two Hundred Thirty Two And Paise Fifty Nine Only
11	10.56	KSRRB M400-17: Providing, laying, spreading and compacting graded stones aggregate to Wet Mix Macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mix method of tipper to site,Laying in uniform layers with paver in subbase/base course on the well prepared surface and compacting with vibratory rollers to achieve the desired density complete as per MORTH specification No. 406.etc with all lead and lifts and as per directions of the Engineer-in-charge(Page No:155 Item No: 20.18, of KPWD SR Bangalore Circle 2018-19)	Cum	2101.14	Rupees Two Thousand One Hundred One And Paise Fourteen Only

12	56.41	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mix finished with flush pointing using white cement, including cost of materials, including cutting, grinding the edge to half/full round wherever required, labour, curing complete as per specification. (P.No. 109, I.No. 14.62 of PWD SR 2018-19)	Sqm	1371.09	Rupees One Thousand Three Hundred Seventy One And Paise Nine Only
13	235.00	KSRB 14.6-1: Providing & laying heavy duty cobble stones 60mm thick interlock pavers, using cement & coarse sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (Avg thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS (P.No 103 of I.No.14.6 in PW,P&IWTDR SR 2018-19)	Sqm	604.63	Rupees Six Hundred Four And Paise Sixty Three Only
14	1469.54	KSRB 14.6-1: Providing & laying heavy duty cobble stones 60mm thick interlock pavers, using cement & coarse sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (Avg thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS (P.No 103 of I.No.14.6 in PW,P&IWTDR SR 2018-19)	Sqm	1171.88	Rupees One Thousand One Hundred Seventy One And Paise Eighty Eight Only
15	270.00	Removing and resetting of kerb stones (P.No.270, I.No.37.57 of PW,P&IWTDR SR 2018-19)	Rmt	110.18	Rupees One Hundred Ten And Paise Eighteen
16	2430.00	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete. (P.No 27 of I.No.5.30 in PW,P&IWTDR SR 2018-19)	No.	454.06	Rupees Four Hundred Fifty Four And Paise Six Only
17	382.53	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 (Page No.180. Item no.24.1 of KPWD S.R Bangalore Circle 2018-2019)	Sqm	89.03	Rupees Eighty Nine And Paise Three Only
18	630.00	Providing chain link fencing 50mm size of 8 gauge properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint (P.No 266 of I.No.37.3 in PW,P&IWTDR SR 2018-19)	Sqm	795.72	Rupees Seven Hundred Ninety Five And Paise Seventy Two Only

	211.30	Above 125%	Sqm	795.72	Rupees Seven Hundred Ninety Five And Paise
19	234.00	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) (P.No 266 of I.No.37.2 in PW,P&IWD SR 2018-19)	m	955.98	Rupees Nine Hundred Fifty Five And Paise Ninety Eight Only
	160.65	Above 125%	m	955.98	Rupees Nine Hundred Fifty Five And Paise Ninety
20	600.00	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint. (P.No.266 I.No.37.4 of PW,P&IWD SR of 2018-19)	m	454.06	Rupees Four Hundred Fifty Four And Paise Six Only
	364.30	Above 125%	m	454.06	Rupees Four Hundred Fifty Four And Paise Six Only
21	23.27	Fabricating, providing and erecting in position Hot dip galvanized Gate. Using 72 x 72 x 4.8mm Sq. G I Pipe Frame with top pipe bending in heavy duty hydraulic press with sand packing and hot bending to form double arch as per drawing profile, 20mm hot dip galvanized sq. rod for verticals at 150mm c/c, as shown in the drawing including providing hot do galvanized forged ornamental design in between rods and heads at top, middle and bottom. Intermediate supports of 75x12mm and 50X6mm arch bent to hot dip galvanized flats. the work is inclusive of throughing GI, flat GI Sqm. rods, placing, welding all the joints including grinding, finishing metal patty, painting two coats enamel painting. The rate is inclusive of all materials Like G I Sq. GI Pipe, GI Forged designs etc., heavy duty hinges are made out of 75mm sold sq. block assembled with 20mm du bearing in three places for each flop. Heavy duty locking arrangement of low places including cost of labour, painting, erection charges using hoist pulley cranes with all lead and lift, loading, transportation, unloading, scaffolding charges and all other incidental charges for successful completion of the work as per directions of the Engineering charge of the work	Sqm	13097.53	Rupees Thirteen Thousand Ninety Seven And Paise Fifty Three Only

22	3578.11	Fabricating, supplying & erecting M.S. angular Truss for all spans as approved design and drawing. The entire truss is anchored suitably by using 4 Nos. of M.S. anchor bolts at each support, with base plate and shoe plate. The work includes cutting, straightening, placing in position of M.S angle and welding wherever necessary, and applying one coat of red oxide primer coat to all the members including cost of all materials, labour charges, & hire charges of machineries for cutting, welding, grinding & erection equipments, etc., complete as per specification. (Page No. 43 Item No. 7.30 of CSR 2018-19).	kgs	142.45	Rupees One Hundred Forty Two And Paise Forty Five Only
23	79.80	KSRB 8.4-1 : Providing and fixing Mangalore tile roofing using first class tiles with necessary special tiles for ridges and hips, teak wood reepers of size 50x25mm and pointed with cement mortar 1:4 over the existing rafters including cost of materials, labour, curing complete as per specifications. Specification No. KBS 8.17. (P.No. 49, I.No. 8.10 of PWD SR 2018-19)	Sqm	1188.57	Rupees One Thousand One Hundred Eighty Eight And Paise Fifty Seven Only
24	1348.70	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. (P 120/ I.15.74 PW, P & IWTD SR - 2018-19)	Sqm	105.72	Rupees One Hundred Five And Paise Seventy Two Only
25	101.84	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 (Page no -5, item no - 2.3)	Cum	339.03	Rupees Three Hundred Thirty Nine And Paise Three Only
26	84.42	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 (Page no -5, item no - 2.3)	Cum	339.03	Rupees Three Hundred Thirty Nine And Paise Three Only
27	50.40	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 (Page no -5, item no - 2.3)	Cum	339.03	Rupees Three Hundred Thirty Nine And Paise Three Only

28	12.92	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @ 465 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth, including cost of all material, labour HOM Machinery curing complete as per specification, (Page. No. 12 Item No. 4.2)	Cum	5889.44	Rupees Five Thousand Eight Hundred Eighty Nine And Paise Forty Four Only
29	33.82	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2(Page No : 15, item No : 4.28)	Sqm	292.54	Rupees Two Hundred Ninety Two And Paise Fifty Four Only
30	295.40	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2(Page No : 15, item No : 4.31)	Sqm	405.93	Rupees Four Hundred Five And Paise Ninety Three Only
31	68.64	KSRB 4-6.5 : Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, post and struts, square / rectangular/ polygon in plan including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (Page No : 16, item No : 4.32)	Sqm	517.05	Rupees Five Hundred Seventeen And Paise Five Only
32	149.50	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for suspended floors, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications upto 3.50m from ground level. Specification No. KBS 4.6.2(Page No : 15, item No : 4.18)	Sqm	453.56	Rupees Four Hundred Fifty Three And Paise Fifty Six Only
33	73.06	KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2(Page No : 16, item No : 4.34)	Sqm	331.10	Rupees Three Hundred Thirty One And Paise Ten Only
34	56.56	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.460 cum, with super plasticisers @ 3 liters conforming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedestals, retaining walls, return walls, walls (any thickness) including attached pilasters, column pillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6 (Page No : 13, item No : 4.11)	Cum	6416.69	Rupees Six Thousand Four Hundred Sixteen And Paise Sixty Nine Only

35	36.34	KSRB 4.2.8: Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplasticiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles, and beams retaining walls, return walls, walls (any thickness) including attached plasters, columns, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6. (Page No : 14, item No : 4.13)	Cum	6680.89	Rupees Six Thousand Six Hundred Eighty And Paise Eighty Nine Only
36	12.23	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 - TMT bars Fe 500 (Page No : 17, item No : 4.46.2)	Tonne	80467.70	Rupees Eighty Thousand Four Hundred Sixty Seven And Paise Seventy Eight Only
37	208.00	Waterproofing of RCC Terrace / podium slab / toilet / utilities / water retaining structure by preparing the surface by chipping and cleaning and Grouting of Honey comb, voids, cracks / construction joints with cement slurry (1kg cement added in 10 ltr of water) added with 100gm of inorganic accelerator, followed by spraying of liquid biological modified alkaline earth silicates @ 0.40 ltr per sqm on whole surface to reduce the micro porosity and allowing it to dry, curing the surface for the silicates to penetrate deeper into the concrete and spraying waterproofing impregnate liquid containing silane and silanol linear copolymer @ 0.50 ltr per sqm and finally applying polymer slurry made out of cross linked acrylic / styrene / butadiene & cement in the ratio of 1:0.1, @0.50kg/sqm on the whole surface, including all labour charges tools and equipments, all complete as per the specification (Page No : 67, item No : 10.5)	Sqm	596.43	Rupees Five Hundred Ninety Six And Paise Forty Three Only
38	64.37	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. specification. No. KBS(Page No : 67, item No : 10.5)	Cum	227.91	Rupees Two Hundred Twenty Seven And Paise Ninety One Only
39	263.03	KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not less than 1800 kg/m ³ and having a minimum average compressive strength 5.00 N/mm ² confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges, scaffolding, curing complete as per specifications. KBS No.5.4(Page No :25, item No : 5.27.1)	Sqm	1034.11	Rupees One Thousand Thirty Four And Paise Eleven Only

40	256.50	KSRB15-3.10 : Providing 20mm thick cement plaster in single coat with cement mortar 1:3, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering. : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	327.69	Rupees Three Hundred Twenty Seven And Paise Sixty Nine Only
41	304.24	KSRB 15.3.1 Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering. : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications..(Page No.112, Item No.15.9)	Sqm	239.25	Rupees Two Hundred Thirty Nine And Paise Twenty Five Only
42	71.95	KSRB15-3-13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering. : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	266.46	Rupees Two Hundred Sixty Six And Paise Forty Six Only
43	304.24	KSRB 15.10.2 Providing white washing for every one additional coat with lime of approved quality, to give an even shade including cost of materials, labour, complete as per specifications. (Page No. 114, Item No. 15.39)	Sqm	6.80	Rupees Six And Paise Eighty Only
44	71.95	KSRB 15.10.4 Providing white washing to ceiling and / or sloping roof surface with additional one coat with lime of approved quality, to give an even shade including cost of materials, labour, complete as per specifications.(Page No. 114, Item No. 15.41)	Sqm	7.94	Rupees Seven And Paise Ninety Four Only
45	256.50	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. - with primer. (P. No. 117, I.No. 15.53.2 of SR 2018-19).	Sqm	115.66	Rupees One Hundred Fifteen And Paise Sixty Six Only
46	304.24	Providing and applying two coats with Plastic emulsion paint of approved brand wall surface to a give an even approved shade after thoroughly brushing the surface,free from mortar drops and other foreign matter, including priming , including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications,with primer. (Page No : 116, item No :15.51.2)For internal walls.	Sqm	102.05	Rupees One Hundred Two And Paise Five Only
47	71.95	Providing and applying two coats with Plastic emulsion paint of approved brand wall surface to a give an even approved shade after thoroughly brushing the surface,free from mortar drops and other foreign matter, including priming , including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications,with primer. (Page No : 117, item No :15.51. 2 & 3) for ceiling	Sqm	102.05	Rupees One Hundred Two And Paise Five Only
48	49.39	Providing vitrified tiles 60 x 60cms of approved make, shade and size for flooring laid on a bed of 12mm thick cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing complete as per specification. (Page No : 107, item No :14.45)	Sqm	1020.50	Rupees One Thousand Twenty And Paise Fifty Only

49	17.06	KSRB 14.14-5: Providing Ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. - for Ceramic Tiles 400 x 400mm on a bed of 20mm thick (Page No : 106, item No :14.36.3)	Sqm	1438.91	Rupees One Thousand Four Hundred Thirty Eight And Paise Ninety One Only
50	97.49	KSRB 14-17.2 : Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. Specification No.KBS 14.16, 14.17 - Colour glazed tiles 30x60 cms 6mm thick with border of size 30 x 10 cms. (P.No.106, I.No. 14.41.2 of PWD SR 2018-19)	Sqm	1850.51	Rupees One Thousand Eight Hundred Fifty And Paise Fifty One Only
51	0.89	KSRB 9.4-3 : Providing Mathi / Nandi wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster grooves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications. Specification No. KBS 9.33 (Page No : 51, item No :9.11)	Cum	1850.51	Rupees One Thousand Eight Hundred Fifty And Paise Fifty One Only
52	9.45	KSRB 9.5-3 : Providing and fixing in position fully panelled Mathi/Nandi wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) Specification No. KBS 9.34 (Page No : 51, item No :9.16)	Sqm	4313.33	Rupees Four Thousand Three Hundred Thirteen And Paise Thirty Three Only
	3.15	Above 125%	Sqm	4313.33	Rupees Four Thousand Three Hundred Thirteen And Paise Thirty

53	17.01	Providing and fixing factory made single leaf rigid GRP Sandwich composite door shutter of 32mm thick, laminated with two GRP skins with wood grain finish, fabricated using U.V. stabilized Isophthalic Gelcoat and on layer of 45 gsm E-Glass Chopped strand Mat (CSM), impregnated with orthophthalic polyester resin. The thickness of the skins shall not be less than 1.5mm. Expanded Polystyrene (EPS) structural foam panel of 29mm thickness and a density of 20 Kg/m ³ shall be used as core material. Wooden reinforcements made of Seasoned Salwood block of cross section not less than 28mmx32mm and also necessary salwood reinforcements for fixing the metal fittings such as tower bolts, aldrops, handles, etc, shall be provided. A structural adhesive compatible with EPS foam shall be used for bonding the core material, the Salwood reinforcement and the skins. The material and process for manufacturing the door shutters shall confirm to RV/TIFAC Composites Design centre Standards and specifications and the door shutters tested in confirmation to IS 4020-1994. The finish of shutter will be plain colour White/Ivory/Beige/Light Grey or any other colour using high quality pigments. Excluding cost of fixtures and inclusive of supply of shutters to respective work spot. (Page No : 58, item No :9.93)	Sqm	3401.68	Rupees Three Thousand Four Hundred One And Paise Sixty Eight Only
54	5.94	KSRB 7.10 : Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using double track window frame section of size 61.85x31.75mm. with 1.2mm thick, bottom section weight 0.695 kg/m, sides and top sections 1.3 mm. thick weight 0.659 kg/m; and shutter comprising top and bottom section of size 40mmx18mm, 1.25mm thick 0.417 kg./m; shutter outer side 40mmx18mm, 1.25mm.thick weight 0.417 kg/m, shutter interlock section 40mmx26.7mm, 1.1mm thick, weight 0.469 kg/m. the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; and providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading aluminium sections including cutting to required length, joints mitred subdividing the frame tenoned and rivetted in the assembled frame stiffened with end clips at corners angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be with necessary steel screws, raul plugs, or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar, aluminium sections pretreated for removal of any Specification No. KBS using aluminium section anodized to 12 - 15 microns. (P.No. 301/ I. No. 7.10.1	Sqm	4794.10	Rupees Four Thousand Seven Hundred Ninety Four And Paise Ten Only
55	9.45	KSRB 15-17.4 : Applying priming coat over new wood surface and / or wood based surface, after brushing with ready mix enamel priming paint including preparing the surface after thoroughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications.(Page. No. 118 Item No. 15.58)	Sqm	56.69	Rupees Fifty Six And Paise Sixty Nine Only

	3.15	Above 125%	Sqm	56.69	Rupees Fifty Six And Paise Sixty Nine Only
56	9.45	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications.(Page. No. 118 Item No. 15.60.1)	Sqm	109.99	Rupees One Hundred Nine And Paise Ninety Nine Only
	3.15	Above 125%	Sqm	109.99	Rupees One Hundred Nine And Paise Ninety Nine Only
57	2.00	KSRB 13-11.1 : Providing and placing on terrace, polyethylene water storage tanks as per IS 12701 : 1996 with manhole lid and suitable locl<ing arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications.(For 1 000 litre capacity) Specification No.KBS 13.22 (P.No.94, I.No.13.78 of PW, P&IWT D S.R 2018-19)	Each	7742.21	Rupees Seven Thousand Seven Hundred Forty Two And Paise Twenty One Only
58	200.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 20mm nominal OD pipes. (P.No.96, I.No. 13.86.2 of PWD SR 2018-19)	m	266.46	Rupees Two Hundred Sixty Six And Paise Forty Six Only
59	100.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 25mm nominal OD pipes(P.No.96, I.No. 13.86.3 of PWD SR 2018-19)	m	332.23	Rupees Three Hundred Thirty Two And Paise Twenty Three Only
60	100.00	KSRB13-8.5 : Providing and fixing to wall, ceiling and floor, low density polyethylene pipes 6.00 kgf/sq.cm working pressure 110mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.15.1 / 13.9(P.No.94, I.No.13.70.4 of PW, P&IWT D S.R 2018-19)	m	430.88	Rupees Four Hundred Thirty And Paise Eighty Eight Only
61	5.00	KSRB 11-15.3 : Providing and fixing 453x357mm dia rectangular shape mirror with plastic moulded frame of approved make and shade with 6mm thick hard board backing including cost of materials, labour complete as per specifications. (P.No.82, I.No. 12.41 of PWD SR 2018-19)	unit	1288.10	Rupees One Thousand Two Hundred Eighty Eight And Paise Ten Only

	1.00	Above 125%	unit	1288.10	Rupees One Thousand Two Hundred Eighty Eight And Paise
62	12.00	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia. (P.No. 88, I.No. 12.111 of PWD SR 2018-19)	Each	170.08	Rupees One Hundred Seventy And Paise Eight
63	12.00	Providing and fixing CI Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot). - 10cms x 7.5cms (P.No. 88, I.No. 12.113.1 of PWD SR 2018-19)	Each	283.47	Rupees Two Hundred Eighty Three And Paise Forty Seven Only
64	12.00	KSRB13-6.1-1 : Providing and fixing in position brass bib cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.2 / 13.3 (P.No. 91, I.No. 13.23 of PWD SR 2018-19)	Each	215.44	Rupees Two Hundred Fifteen And Paise Forty Four Only
65	6.00	KSRB13-6.3-3 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.6 / 13.3. (P.No.91/ I.No. 13.34 of CSR 2018-19)	Each	509.12	Rupees Five Hundred Nine And Paise Twelve Only
66	6.00	Constructing brick masonry inspection chamber 450x450mm, and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS 450x450mm and 450mm depth (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 450x450mm (P.No. 73/ I.No.11.50.2 of PWD SR 2018-19)	Nos	6009.63	Rupees Six Thousand Nine And Paise Sixty Three Only
67	9.00	KSRB 11-2 : Providing and fixing white vitreous china clay, water closet Orissa pattern of size 580 x 440mm with integral type footrests, 100mm S or P trap, 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 32mm diameter flush pipe fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11. (P.No. 77, I.No.12.2 of PWD SR 2018-19)	Each	4789.56	Rupees Four Thousand Seven Hundred Eighty Nine And Paise Fifty Six Only

68	6.00	KSRB 11-7.1 : Providing and fixing white vitreous china clay, flat back, lipped front urinal basin of 430x260x350mm with 5 litres PVC automatic flushing cistern, C.I / M.S brackets, standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps complete painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11 (P.No.79 I.No.12.7 of CSR 2018-19)	unit	3483.32	Rupees Three Thousand Four Hundred Eighty Three And Paise Thirty Two Only
69	50.00	KSRB 12-1.2 : Providing and laying in position to required level or slope 150mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints, including cost of materials, labour charges complete as per specifications. Specification No. KBS 12.2.5 / 12.7 (P.No.70 I.No.11.2 of CSR 2018-19)	m	417.27	Rupees Four Hundred Seventeen And Paise Twenty Seven Only
70	30.00	Providing and laying reinforced cement concrete pipe NP2 for culverts including pointing ends, and fixing collars with cement mortar 1:2 including cost of all materials, labour, curing complete as per specifications. Specifications. No. KSRB 1000, 2300 MOST Specification No.1000 / 2300 - -150mm dia (P.No.246, I.No.34.7.1 of CSR 2018-19)	m	443.35	Rupees Four Hundred Forty Three And Paise Thirty Five Only
71	2.00	Providing Square Tank Covers of size 24" X 24" at 21kgs(Page No : XXXVI)	Each	1336.52	Rupees One Thousand Three Hundred Thirty Six And Paise Fifty
72	10.00	Providing Footsteps of size 15" X 14" Heavy (Page No : XXXVI)	Each	290.82	Rupees Two Hundred Ninety And Paise Eighty
73	167.24	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(b) / 2.3.5	Cum	222.36	Rupees Two Hundred Twenty Two And Paise Thirty Six Only
74	3.94	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 - (1:4:8 - (M7.5)) with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2	Cum	5677.99	Rupees Five Thousand Six Hundred Seventy Seven And Paise Ninety Nine Only
75	58.30	Providing and laying reinforced cement concrete pipe NP3 for culverts including pointing ends, and fixing collars with cement mortar 1:2 including cost of all materials, labour, curing complete as per specifications. Specifications. No. KSRB 1000, 2300 MOST Specification No.1000 / 2300 - - 300mm. dia	Mtr	1707.18	Rupees One Thousand Seven Hundred Seven And Paise Eighteen Only

76	88.00	Providing and laying reinforced cement concrete pipe NP2 for culverts including pointing ends, and fixing collars with cement mortar 1:2 including cost of all materials, labour, curing complete as per specifications. Specifications. No. KSRB 1000, 2300 MOST Specification No.1000 / 2300 - - 1200mm dia	Mtr	6274.50	Rupees Six Thousand Two Hundred Seventy Four And Paise Fifty Only
77	29.84	Filter media stone aggregate 60mm &down size	Cum	1407.98	Rupees One Thousand Four Hundred Seven And Paise Ninety
78	29.84	Crushed stone aggregate 13.2mm to 10mm	Cum	1457.58	Rupees One Thousand Four Hundred Fifty
79	12.43	Sand/ Artificial Sand/ Manufactured Sand	Cum	2125.31	Rupees Two Thousand One Hundred Twenty Five And Paise
80	50.00	Executive bench made out of sadaralli grey stone with hand suport 3 line finishing with arch desiagn with 100cm slabs height 90% length 45cms (data approved rate)	No's	19108.18	Rupees Nineteen Thousand One Hundred Eight And
81	22.00	Supplying and Fixing of Garbage bins rectangular with permanent structure series without arch 100litre capacity approved by Engineer in charge	No's	19370.66	Rupees Nineteen Thousand Three Hundred Seventy And Paise Sixty Six
82	2.00	Geophysical investigation of site for Sinking borewell for supplying drinking water to the habitations either through the hand pump,MWS,P.W.S.S by vertical electrical sounding by adpoting venner or Schlumberger's method,including reconnaissance survey of Geological formation. Geophysical investigation of existing ground indecundity its quality & acceptability of the users indicating the location of site,recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 metre inconsolidated formation for proper seating of casing pipe,depth of drilling required to cover full depth of aquifer proposed to be tapped,probable yield and other information required including transportation of instrument and accesories to work site,engaging technical personal and labour required etc.,(PRED SR 2012-13 It.9.4, P-47) (PRED SR 20-05-2019 It.13.04)	BW	3956.02	Rupees Three Thousand Nine Hundred Fifty Six And Paise Two Only
83		Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over burden upto 20 M fixing of casing pipes, collars and cap with necessary cutting and threading including transportation of rig and supporting vehicals, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour .(excluding cost of casing pipes, collars, cap ect.) (PRED SR 20-05-2019 It.13.01,)			Rupees Nil
a	100.00	0 to 50 m	Rmt	364.32	Rupees Three Hundred Sixty Four And Paise
b	100.00	50 to 100 m	Rmt	464.06	Rupees Four Hundred Sixty Four And Paise Six Only

c	100.00	100 to 150 m	Rmt	478.75	Rupees Four Hundred Seventy Eight And Paise
d	100.00	150 to 200 m	Rmt	562.75	Rupees Five Hundred Sixty Two And Paise Seventy Five Only
e	100.00	200 to 250 m	Rmt	665.64	Rupees Six Hundred Sixty Five And Paise Sixty
f	100.00	250 to 300 m	Rmt	734.93	Rupees Seven Hundred Thirty Four And Paise Ninety Three Only
g	100.00	300 to 350 m	Rmt	866.17	Rupees Eight Hundred Sixty Six And Paise
84	24.00	Providing and fixing 250mm dia PVC (casing pipe) (page no.XXXI, SL no.909) (KPWD SR 2016-17)	Rmt	2729.74	Rupees Two Thousand Seven Hundred Twenty Nine And Paise
85	60.00	Supply of ISI Mark 175mm nominal Bore, Plain end steel casing Pipe-grade of steel Fee 4100 of wakk thickness 504mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel electric or basic oxygen process in fandum length of 5 to 7mtr. Both ends threaded confirming to Is554/1985 one end fixed with socket confirming to IS 270:2001 and other end with screwed pipes. All pipes shall be reasonably free from defectes. The tubes shall be resonably straigth should be with ISI Marking Weighting 25.10 kg/mtr (Inclusive of all taxes and durties) Prices include Collar - medium duty. (Page No.III,Ilt no.84)PRED SR 2012-13.	Rmt	1391.12	Rupees One Thousand Three Hundred Ninety One And Paise Twelve Only
86	10.00	Providing 175mm Dia M.S. Collar (P.No.iii,I.No.86) PRED SR 2012-13	No	157.49	Rupees One Hundred Fifty Seven And Paise Forty Nine Only
87	2.00	Providing 175mm dia Bore Cap CE (M) (P.No.iii,I.No.85) PRED SR 2012-13	No	104.99	Rupees One Hundred Four And Paise Ninety Nine
88	2.00	Atalanta suguna CRI KIRLOSKAR and other equipments pumps 10.00 HP/7.5 KV (20 stage) (Pg No. XLI. Sl.no.29) KPWD SR-2018-19	No	52447.75	Rupees Fifty Two Thousand Four Hundred Forty Seven And Paise
89	600.00	Providing and fixing in trenches galvinised/mild steel tube 50mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for seperately) including cost of all materials, labour charges,HOM of equipment and testing complete as per specifications. Specification No. KBS 13.2.14/13.6 (page no.92/Ilt no.13.15)KPWD SR 2018-19.	Rmt	431.80	Rupees Four Hundred Thirty One And Paise Eighty Only

90	1220.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 to IS 8130-1984 and virgin grade PVC insulation and power coating extruded PVC sheathed suitable for working voltage upto 1100 volts with specified IS 694:1990 and confirming to the attached GTP of group A 3CX4.0 sq.mm (PWD Ele SR 2014-15,P-12/It-2.10.3)	Rmt	133.02	Rupees One Hundred Thirty Three And Paise Two Only
91	2.00	Providing and fixing in position 50mm Nominal bore non-return valve vertical type of approved make including cost of all materials,labour and HOM of equipment with all leads complete as per specifications.(PWD SR 18-19,P-95/It no.13.62)	No	1412.26	Rupees One Thousand Four Hundred Twelve And Paise Twenty Six Only
92	2.00	Supplying and fixing 50mm GI Union.(PWD SR 2016-17,P-XXXIX)	No	234.86	Rupees Two Hundred Thirty Four And Paise Eighty Six Only
93	2.00	Supplying and fixing 50mm GI Elbow.(PWD SR 2016-17,P-XXXIX)	No	117.38	Rupees One Hundred Seventeen And
94	2.00	Supplying and fixing 50mm GI Nipple.(PWD SR 2016-17,P-XXXIX)	No	109.50	Rupees One Hundred Nine And Paise Fifty Only
95	100.00	Supplying and fixing 50mm GI Hose colleres(PWD SR 2016-17,P-XXXIX)	No	108.14	Rupees One Hundred Eight And Paise Fourteen
96	2.00	Supplying and fixing 20" x 20" x 2.5" polished wood board made of not less than 15mm thick plank on both the sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., P.no.44 / 1 no. 6.6.6 KPWD ELE SR 2014-15	No	317.07	Rupees Three Hundred Seventeen And Paise Seven Only
97	2.00	Supplying and fixing miniature circuit breakers on existing MCB distribution board using necessary fixing materials and 'C' type curve indicator ON/OFF energy cross-3 with short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.(PWD Ele SR 2014-15,P-47/Sl no.6.16.6) 40-63 Amps	No	2032.61	Rupees Two Thousand Thirty Two And Paise Sixty One Only
98	2.00	Supplying of TPST with rewirable porcelain channels in SM encloser made out of 14 SWG powder coated point of approved colour 32 amps (PWD Ele SR 2014-15,P-44,It-6.5.1)	No	1961.21	Rupees One Thousand Nine Hundred Sixty One And Paise Twenty
99	2.00	Supplying and fixing LED type panel board indicating lamp with required colour suitable for 220 V AC 50 HZ 12/24 V DC(PWD Ele SR 2014-15,p-48,Sl no.6.36)	No	464.06	Rupees Four Hundred Sixty Four And Paise Six
100	2.00	Supplying fully automatic star delta starter unit push button type with suitable wires 2 conductors and adjustable thermal timer mounted on a common base plate held in steel enclosure for use on 400/440 volts phase and wired after fixing to the existing wooden board for motor. upto 12.5HP(PWD Ele SR 2014-15,p-44,Sl no.-6.2.1)	No	6911.49	Rupees Six Thousand Nine Hundred Eleven And Paise Forty Nine Only
101	2.00	Supplying and fixing single phase preventer using necessary wires over an existing panel board suitable for motor up to 20 HP capacities.(PWD Ele SR 2014-15,p-44/Sl no.6.3)	No	806.32	Rupees Eight Hundred Six And Paise Thirty Two

102	40.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade multistrand copper conductor single core wire in open or concealed system of wiring as per IS 694:1990 & conforming to the attached GTP of group A. 4 sqmm (PWD Ele SR 2014-15,p-6,lt-2.5.4(d))	Mtrs	44.20	Rupees Forty Four And Paise Twenty Only
103	8.00	Supplying fixing and wiring heavy duty low voltage capacitors conforming to IS 2834 phase 400/440 volts grade, for power factor improvement of rotating machinery.(PWD Ele SR 2014-15,p-48/SI no.6.35)	No	434.66	Rupees Four Hundred Thirty Four And Paise Sixty Six Only
104	2.00	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cotouts and other equipments on the meter board using 40mm dia 2.90 thick GI pipe 2.5 mtr long buried in a pit... The pit should be filled with equal proportion of salt and charcoal 150mm alround the pipe to complete depth. The connection from the to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia (PWD Ele SR 2014-15,p-55,SI no.7.1)	No	2863.08	Rupees Two Thousand Eight Hundred Sixty Three And Paise Eight Only
105	16.00	Digging of trench of 0.36mtrs deepx0.5 mtrs wide refilling the trench to the required gorund level and consolidating etc., complete (PWD Ele SR 2014-15,p-62,lt-7.9.2) hard soil	Mtrs	111.29	Rupees One Hundred Eleven And Paise Twenty
106	20.00	Supplying laying 1.1 KV class LT UG cable having aluminium conductor PVC insulated extruded inner shethed galvanised steel strip (excep 2cx 10 sqmm wire armoured) confirming to IS-3975:1990 (No. of strip indicated in GTP) and extruded PVC outer sheathed armoured cable with specified IS-1554,part-1:1988 and confirming to the attached GTP of group A 4 core 16 sq mm PWD Ele SR 2014-15,p-55,lt-7.4.4)	Mtrs	147.41	Rupees One Hundred Forty Seven And Paise Forty One Only
107	50.00	Labour charge for laying 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe/ on wall / on poles as required in existing trench/duct. 6 sq mm to 16 sq mm(PWD Ele SR 2014-15,p-61,lt-7.8.1)	No	11.34	Rupees Eleven And Paise Thirty Four Only
108	4.00	Supplying and fixing class-A(medium duty) GI pipe wall thickness not less then 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1KV class 40mm(PWD Ele SR 2014-15,p-62,lt-7.12.1)	Rmt	362.22	Rupees Three Hundred Sixty Two And Paise Twenty Two Only
109	2.00	Supplying and fixing LT cast iron pot heads suitable for 1.1KV class UG cable filled with necessary bitumen / insulating compound complete with terminals,clamps bolts and nuts and washer etc.,complete for 16 sq mm as per specifications.(PWD Ele SR 2014-15,p-62,lt-7.13.2)	No	293.97	Rupees Two Hundred Ninety Three And Paise Ninety Seven Only
110	6.00	Supplying and fixing porcelain fuse channel with cut out on the existing wooden block and wiring complete 63 amps(PWD Ele SR 2014-15,p-45,lt-6.7.3)	No	245.68	Rupees Two Hundred Forty Five And Paise Sixty Eight Only
111	72.00	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials upto a lead of 1000 meters, stacking serviceable and unserviceable materials seperately complete as per specifications. MORTH Specification No. 202 (KPWD SR 2018-19, P-140, lt 18.47)	Cum	1000.49	Rupees One Thousand And Paise Forty Nine Only

112	108.00	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(b) / 2.3.5 (KPWD SR 2018-19, P-6, It-2.4)	Cum	499.69	Rupees Four Hundred Ninety Nine And Paise Sixty Nine Only
113	400.00	Providing and fixing Chlorinated Poly Vinyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (external work) - 50mm nominal OD pipes (KPWD SR 2018-19, P-99, It-13.87.6)	Mtr	480.77	Rupees Four Hundred Eighty And Paise Seventy Seven Only
114	40.00	Making connection of G.I. distribution branch with G.I. main of 25mm to 40mm. Nominal bore, including cutting and threading the pipes, providing and fixing Tee, nuts, labour for all item of works, testing and HOM of equipments complete as per specifications. (P.No.93/ I.No. 13.20 of KPWD SR 2018-19)	Each	537.53	Rupees Five Hundred Thirty Seven And Paise Fifty Three Only
115	440.00	Providing and fixing Chlorinated Poly Vinyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling & testing of joints complete. (external work). - 20mm nominal OD pipes (KPWD SR 2018-19, P-98, It-13.85.2)	Mtr	174.72	Rupees One Hundred Seventy Four And Paise Seventy Two Only
116	200.00	Providing and fixing to wall, ceiling and floor Medium density polyethylene pipes 6.00 kgf/sq.cm working pressure 25mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No. KBS 13.2.15.1 / 13.9 (KPWD SR 2018-19, P-95, It-13.67)	Mtr	143.56	Rupees One Hundred Forty Three And Paise Fifty Six Only
117	75.60	KSRB 2-4 : Refilling available around earth pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. And lift upto 1.5m. Including cost of all labour complete as per specifications. (KPWD SR 2018-19, P-7, it-2.11)	Cum	134.66	Rupees One Hundred Thirty Four And Paise Sixty Six Only
118	104.40	Loading and unloading of stone boulder/stone aggregates/sand/kanker/ moorum. KSRRB M100-1: Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 (KPWD SR 2018-19, P-136, it.17.1)	Cum	73.28	Rupees Seventy Three And Paise Twenty Eight Only
119	2.00	KSRB 2-4 : Providing and fixing in position brass gate valve with C.I. wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. (P.No.94/ I.No. 13.37 of KPWD SR 2018-19)	Each	1935.32	Rupees One Thousand Nine Hundred Thirty Five And Paise Thirty Two Only

120	40.00	KSRB13-6.2-1 : Providing and fixing in position brass stop cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.2 / 13.3 (Pg No:- 93/I.No:-13.26 of KPWD SR 2018-19 2018-19)	Each	156.92	Rupees One Hundred Fifty Six And Paise Ninety Two Only
121	54.00	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No. 4.3 of KPWD SR 2018-19)	Cum	5677.99	Rupees Five Thousand Six Hundred Seventy Seven And Paise Ninety Nine Only
122	36.00	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M 20 for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, for foundations & sub-structure works with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) (P.No.18, I.No. 4.48 of KPWD SR 2018-19)	Cum	6058.59	Rupees Six Thousand Fifty Eight And Paise Fifty Nine Only
123	2.00	BESCOM deposit Charges and miscellaneous	No	12598.80	Rupees Twelve Thousand Five Hundred Ninety

[Handwritten signature]
JAE

[Handwritten signature]
Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92